

**CSIR-NORTH EAST INSTITUTE OF SCIENCE & TECHNOLOGY
(COUNCIL OF SCIENTIFIC AND INDUSTRIAL RESEARCH)**

Jorhat Assam 785 006

Name of Work : Replacement of existing damaged wooden partition wall of purchase section with aluminium partition wall and sealing of windows of tissue culture room of biotechnology block.

SCHEDULE OF QUANTITIES

Sl. No.	Item description	Unit	Qty.	Rate in Figure	Rate in Words	Amount
1	Dismantling all types of ceiling, partition and wall lining and stacking the materials as directed by the department for all levels	Sqm	19.040			
2	Providing, fitting and fixing anodised aluminium framed glazed doors with partition walls partly glass and partly prelaminated board with anodised aluminium frame made of 100mm x 43mm x 2mm sections of approved brand with doors style of size 81mm x 43mm x 2mm, top rails 46mm x 43mm x 2mm, lock rails 81mm x 43mm x 2mm, fitting with glazing clip, special rubber type gasket complete including hydraulic floor spring pivot aluminium door handle lock angles cleat etc. complete as directed by the department at all levels. (i)6mm thick glass panes and 12mm prelaminated board	Sqm	19.040			
3	Providing, fitting and fixing anodised aluminium sliding windows and ventilators of standard sections of approved brand without horizontal glazing bars, joints mitred and welded (manufactured to relevant IS specifications) and providing and fixing handles, angle cleat, rubber gasket, roller, bolting device, locking arrangements, screws etc as required complete as specified and directed for all levels.2 Track sliding window. 5 mm coloured glass	Sqm	4.500			
4	Dismantling of existing steel windows/ steel ventilators/ steel windows and steel ventilators without damaging the walls, removing to a safe place and necessary repairs to the edges of walls.	Sqm	8.370			
5	Brick work in cement mortar with 1st class brick including racking out joints and curing complete as directed.(II) In superstructure above plinth level up to 1st floor level.	Cum	1.925			
6	15 mm thick Cement plaster in single coat on single or half brick wall for interior plastering up to 1st floor level including arises, internal rounded angles, not exceeding 80mm girth and finished even and smooth including curing complete as directed.On rough side, In cement mortar 1:6	Sqm	8.370			

**CSIR-NORTH EAST INSTITUTE OF SCIENCE & TECHNOLOGY
(COUNCIL OF SCIENTIFIC AND INDUSTRIAL RESEARCH)
Jorhat Assam 785 006**

Name of Work : Replacement of existing damaged wooden partition wall of purchase section with aluminium partition wall and sealing of windows of tissue culture room of biotechnology block.

SCHEDULE OF QUANTITIES

Sl. No.	Item description	Unit	Qty.	Rate in Figure	Rate in Words	Amount
7	Providing two coats of Birla White Wall Care Putty (Water Resistant White Cement based putty for concrete/ mortar walls and ceiling both internal and external) after removing all loosely adhering material from the wall surface with the help of emery stone, putty blade or wire brush and moistening the wall with sufficient quantity of clean water as specified and directed by the department. (Total thickness of two coats is maximum 1.5mm).(ii)Thickness = 1.0mm thick	Sqm	16.740			
8	Wall painting (two coats) with acrylic emulsion paint approved brand and manufacture (Asian paint/ Berger paint/ ICI paint/ J & N paint/ Nerolac) on new surface to give an even shade after thoroughly brushing the surfaces free from mortar droppings and other foreign matter and sand papered smooth. Acrylic Emulsion Paint approved brand and manufacture (Asian paint/ Berger paint/ ICI paint/ J & N paint/ Nerolac)	Sqm	365.110			

Total Rs.

(Rupees.....)only.

N.B.

1. The work will be executed as per CPWD's Specifications and norms.
2. Rates should be quoted both in words and in figure.

Signature of the Contractor

Address _____

