

**CSIR-NORTH EAST INSTITUTE OF SCIENCE & TECHNOLOGY  
(COUNCIL OF SCIENTIFIC AND INDUSTRIAL RESEARCH)  
Jorhat Assam 785 006**

**NAME OF WORK: Replacement of External Old Waste Pipes of RCC B-type quarters with PVC pipes**

**SCHEDULE OF QUANTITIES**

Sl. No	Description of Item	Unit	Qty	Rate in Figure	Rate in Words	Amount
1	Earthwork in excavation for foundation trenches of walls, retaining walls, footings of column, steps, septic tank etc. including refilling (return filling) the quantity as necessary after completion of work, breaking clods in return filling, dressing, watering and ramming etc. and removal of surplus earth with all lead and lifts as directed and specified in the following classification of soils including bailing out water where necessary as directed and specified . Upto a depth of 2.00 m below the existing ground level. In ordinary soil.	<b>Cum</b>	<b>40.86</b>			
2.	Supplying, fitting and fixing PVC pipes of 6 kg/cm <sup>2</sup> (Supreme/Prince) or other ISI approved including joining, fitting and fixing with PVC coupler, reducer, socket plug, door-elbow, door-tee, door bend, door Y, clamps etc as necessary complete as directed and specified. In exposed surfaces or in trenches including breaking brick wall/CC/RCC and making good to the damages 110 mm dia	<b>Rm</b>	<b>360.00</b>			

Sub Total Rs.

**CSIR-NORTH EAST INSTITUTE OF SCIENCE & TECHNOLOGY  
(COUNCIL OF SCIENTIFIC AND INDUSTRIAL RESEARCH)  
Jorhat Assam 785 006**

**NAME OF WORK: Replacement of External Old Waste Pipes of RCC B-type quarters with PVC pipes**

**SCHEDULE OF QUANTITIES**

<b>Sl. No</b>	<b>Description of Item</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate in Figure</b>	<b>Rate in Words</b>	<b>Amount</b>
3	Supplying, fitting and fixing PVC pipes of 6 kg/cm <sup>2</sup> (Supreme/Prince) or other ISI approved including joining, fitting and fixing with PVC coupler, reducer, clamps etc as necessary complete as directed at all levels including below GL as directed and specified. In exposed surfaces or in trenches including breaking brick wall/ CC/RCC and making good to the damages. 160 mm dia	<b>Rm</b>	<b>166.00</b>			

**Grand Total Rs.**

**Rupees**

( \_\_\_\_\_ ) only.

**N.B.**

1. The work will be executed as per CPWD's Specifications and norms.

2. Rates should be quoted both word and figure.

Signature of Contractor

Address-----

-----