

CSIR-NORTH EAST INSTITUTE OF SCIENCE & TECHNOLOGY  
(COUNCIL OF SCIENTIFIC AND INDUSTRIAL RESEARCH)  
Jorhat Assam 785 006

NAME OF WORK: **Renovation of frontage and sides of CSIR-NEIST Auditorium.**  
**SCHEDULE OF QUANTITES**

Sl. No	Description of Item	Unit	Qty	Rate in Figure	Rate in Words	Amount
1	Providing, fitting, hoisting and fixing of roof trusses fabricated out of combination of any two or all of the following sections (i) Square section (ii) Rectangular Hollow section of specification RSH/SHS and (iii) M.S. circular hollow section of Grade 210 including purlins, bottom runners and providing M.S. cleat, M.S. angle base plank, bolts and nuts with red oxide primer including fitting bottom runner and cleat etc. for fixing ceiling joist as per design complete as directed as per specifications. b) Using other ISI marked approved brand tube	Qtl	59.90			
2	Providing, fabrication and fixing of structural glazing made out of Anodized aluminium mother frame 6 nos 1.2m each @ 1.819 Kg/m and sub frame of 16 nos. 0.60 m each @ 0.31 Kg/m of Jindal or equivalent and 5 mm reflective glass of approved shade. The glass to be pasted using structural silicon (DC 995) and weather seal silicon to be used (DC 789), the structure complete with all accessories as and where necessary.	Sqm	36.00			
3	Providing plain Polycarbonate transparent sheet roofing at all levels with self drilling, self tapping screws complete (Roof trusses, purlins etc. to be measured and paid separately.) (ii) 2.00 mm thick	Sqm	266.40			
4	Supply and installation of 3.00 mm thick aluminium composite panel (A.C.P) of Alston or equiv. make with a skin thickness of 0.25 mm on each side and non toxic polyethene core of 2.5mm to be installed by forming try on aluminium hollow tube in the size of 38mm x25mm x1.20mm .The ACP should be of PVDF coated by EIF ATOCHEM, KYNAR 500 (Min 70%) for high quality, even finish and long lasting colours on the front side and back side should polyester paint. The expansion joints are to be fitted with weather silicon in column and wall.	Sqm	322.42			

Grand Total Rs.

CSIR-NORTH EAST INSTITUTE OF SCIENCE & TECHNOLOGY  
(COUNCIL OF SCIENTIFIC AND INDUSTRIAL RESEARCH)  
Jorhat Assam 785 006

NAME OF WORK: **Renovation of frontage and sides of CSIR-NEIST Auditorium.**

**SCHEDULE OF QUANTITIES**

Sl. No	Description of Item	Unit	Qty	Rate in Figure	Rate in Words	Amount
5	Removing white or colour wash by steel wire brushing and/ or scraping, sand papering and preparing the wall surface smooth including necessary repairs to scratches complete.	Sqm	741.28			
6	Finishing wall with two coats of acrylic emulsion exterior coatings of Unicem "Rakshak" brand of required shade by thinning 1ltr. of paint with 750ml of water to give an even shade after thoroughly brooming the surfaces to remove all dirt and remains of loose powdered materials as specified and directed by the department.	Sqm	741.28			

Grand Total Rs.

Rupees (.....) Only.

- NB:
1. Rate must be quoted both in word and figure.
  - 2 All work will be executed as per CPWD's norms.