

CSIR-NORTH EAST INSTITUTE OF SCIENCE & TECHNOLOGY
(Council of scientific and industrial research)

NAME OF WORK : Supplying, installation, commissioning and testing of Chemical Earthing at CSIR-NEIST, Jorhat

Sl No	Particulars of the item	Qty	Unit	Rate in figures in	Rate in words	Amount in Rs.
1	Supplying with installation & commissioning of readymade maintenance free CPRI approved chemical earthing system with 50 mm dia 3.00 metres length corrosion free single pipe technology copper CHEMRODE ELECTRODE complete with RESLOW grouting minerals 25 K and advance Earth Pit cover including excavation of earth pit and construction of brick earth chamber including plastering both inner & outer surface of brick wall as specified and directed by the deptt.	15	Each			
2	Supplying & laying of 25 x 5 mm size copper strips drawn on surface from earth electrode to electrical switchgears, machineries etc complete with supply of brass nuts & bolts, screws etc including 32 mm dia covering GI pipe, reveting, soldering & making necessary connection as approved and specified by the deptt.	150	Mtrs			
	Total Estimated Cost in Rs.					

NB: Rate must be written both figures and words