

NAME OF WORK : 1. Dismantling and re-fitting of street light line in front of General Stores at CSIR-NEIST, Jorhat

Sl No	Particulars of the item	Qty	Unit	Rate in figures in	Rate in words	Amount in Rs.
1	Supplying and laying of 3 x 25 sq.mm. size PVC insulated and sheathed aluminium stranded armoured underground cable laid in ground/partially in air including excavation of cable trench up to 30cm x 75cm depth refilling, protecting brick covering , sand cushion etc complete handling surplus soil in proper place and proper size of cable lug, cable arrow mark as specified and directed by department. (Havells/Finolex/Polycab Make)	130	Mtrs			
2	Dismantling of RCC existing pole and carrying of damage materials to the departmental/general stores as directed by depatt.	1	Each			
3	Dismantling of over head 3 phase 4 wires bare copper conductor and carrying to departmental stores/general stores as directed by deptt	70	Mtrs			
4	Shifting of existing street light panel board from existing position to new position complete with all necessary re-installation and connectiopn as required.	1	Each			
5	Supplying including fitting and fixing of resing cast type 1.1 kV PVC cable straight through jointing kits (MS-SEAL Make) including all accessories for the 16 sq.mm cable including testing and commissioning as directed and specified by deptt	2	Each			
	Total quoted amount in Rs.					

NB: Rate must be written both figures and words